


15-039-00471-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Decatur County. Sec. 12 Twp 2S Rge. 28 (~~W~~) (W)
Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Union Texas Petroleum
Lease Name Reeves Well No. 1
Office Address 1000 Liberty Bank Building, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed September 10 19 62
Application for plugging filed September 10 19 62
Application for plugging approved September 10 19 62
Plugging commenced September 10 19 62
Plugging completed September 10 19 62
Reason for abandonment of well or producing formation no oil or gas found in commercial quantities
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 550' and cement through drill pipe with 20 sacks. Set plug @ 180' and cement through drill pipe with 20 sacks. Set plug and 1/4 sack of hulls at 35' of base of cellar and cap with 110 sacks, plugging completed 7:45 PM on September 10, 1962

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1962

CONSERVATION DIVISION
Wichita, Kansas

9-17-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 412 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains - Partner (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
412 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 62

My commission expires JANET JOHNSON
My commission expires Jan. 25, 1963

Janet Johnson
Janet Johnson Notary Public.



15-039-00471-00-00

ROTARY DRILLING LOG

Operator: Union Texas Petroleum
No. 1 V. Reeves
NW SE Sec. 12-2S-28W
Decatur County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 9/4/62
Completed: 9/10/62

Remarks: Set 214' of 8 5/8" with
175 sacks HA5 , plug down
at 11:30 PM

FORMATIONS:

Sandy Soil	10'
Shale	212'
Shale & Sand	975'
Shale & Lime	1115'
Sand & Shale	1450'
Shale	2049'
Anhydrite	2081'
Shale	2100'
Shale & Lime	2944'
Shale	3060'
Lime & Shale	3108'
Lime	3378'
Lime & Shale	3424'
Lime	3555'
Lime & Sand	3575'
RTD (D&A)	3575'

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1962

CONSERVATION DIVISION
Wichita, Kansas

9-17-62

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By: *Wilson Rains*
Wilson Rains - Partner

subscribed and sworn to before me, a notary public, in and for the State of Kansas, County of Sedgwick, this 14th day of September, 1962.

My Commission expires:

JANET JOHNSON

My commission expires Jan. 25, 1965

Janet Johnson
Janet Johnson Notary Public