

15-039-19023-00-02

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

Washed down
 API NUMBER 11-24-62
 LEASE NAME Olive Waterflood
 (Anna Miller)
 WELL NUMBER Water Source Well (#2)

660 Ft. from S Section Line
4620 Ft. from E Section Line

SEC. 12 TWP. 2S RGE. 28 ~~KEXOK~~(W)

COUNTY Decatur

Date Well Completed 11-24-62

Plugging Commenced 2:00 P.M.
4-24-90

Plugging Completed 2:45 P.M.
4-24-90

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Water Supply

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 14, 1990 (date)

by District #4 (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation Cedar Hills Depth to Top 1745' Bottom 1755' T.D. 1755'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hills	water	1745'	55'	8-5/8"	178'	-0-
				5-1/2"	1745'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The casing was perforated 3 shots @ 1300' prior to cementing. Down 5-1/2" casing @ 400# maximum pressure. Mixed 2 sks. hulls w/125 sks. cement and shut in @ 200#. Down 8-5/8" casing @ 400# maximum pressure. Mixed 1 sk. hulls w/50 sks. cement and shut in @ 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135

Address P.O. Box 352, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (~~Employee of Operator~~ Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 90

Margaret A. Schulte
 Notary Public

My Commission Expires:



Margaret A. Schulte

APR 30 1990
 04-30-90
 WICHITA DIVISION
 WICHITA, KANSAS

WELL LOG

15-039-19023-00-02


COMPANY Murfin Drilling Company

SEC. 12 T. 25 R. 28W
LOC. C/SW SW

FARM ANNA MILLER #2 NO. Two (SALT WATER DISPOSAL)

RIG. NO. 8
TOTAL DEPTH 1755'
COMM. 11/23/62 COMP. 11/24/62
SHOT OR TREATED No
CONTRACTOR ISSUED Murfin Drilling Company

COUNTRY Decatur
KANSAS



CASING
20 10
15 8
12 6
13 5 1/2" 1745' with 50 sacks cement

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Washed out old hole to 1755' and set 5 1/2"

State of Kansas
County of Sedgwick ss:

I, Fred Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the ANNA MILLER #2 SWD well.

APR 30 1990
WICHITA, KANSAS

Subscribed and sworn to before me this 13th day of February 19 63

Fred Murfin
By am

My Commission Expires: June 14, 1964

May Paul Blumel
NOTARY PUBLIC