

15039-20643-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 13 TWP. 2 S RGE. 28W E/W
 Location as in quarters or footage from lines:
2310 FSL & 4780 FEL of section

*			

Locate Well
 correctly on above
 Section Platt.

Lease Owner S & W Drilling Co.
 Lease Name Lemoine Rush Well No. 1
 Office Address P O Box 132 Oberlin, Ks. 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 9-21-82
 Application for plugging filed 12-10-84
 Plugging commenced 9:00 AM Dec. 8, 1984
 Plugging completed 10:10 AM Dec 8, 1984
 Reason for abandonment of well or producing formation non commercial
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation Lansing -KC Depth to top 3440 bottom 3639 T.D. 3680
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Fresh ground water	water	0	170	8 5/8	255	0
Ogallala						
Lansing- Kc	oil, salt wtr	3440	3639	5 1/2	3678	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. 5 1/2" casing was pumped down with 75 sacks of cement mixed with 4 sacks of hulls followed by 20 sacks of gel followed by 125 sacks of cement. The annulus between the 5 1/2 and 8 5/8 casing received and additional 100 sacks of cement. all cement was 50/50 poz with 6% gel and 3% CC.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 12 1984

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Halliburton Oberlin, Ks. CONSERVATION DIVISION
 Wichita, Kansas
12-12-84

STATE OF _____ COUNTY OF _____, ss.
 _____ (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James L Reed
Oberlin, Ks
 (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of DECEMBER, 1984

Arthur S. Dale
 Notary Public.

My Commission expires: 12/22/86