

6 031284

API NUMBER 15- 9-25 039-20,679-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE SW, SEC. 14, T 2 S, R 28 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6467  
Operator: West Kansas Oil Corp  
Name & Address: 403 N. Elk  
Oberlin, Ks. 67749

Lease Name Heaton Well # 1  
County Decatur 119.60  
Well Total Depth 3680 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 139

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: Day: 25 Month: Sept Year: 19 89

Plugging proposal received from Young

(company name) West Kansas Oil Corp (phone)

were: 8 5/8" set at 139' w/125 sks cwc. 4 1/2" set at 3663' w/TOC at 2656' bond log.

2 shots at 1450'. Order 250 sks 65/35 poz 10% gel 2% dicel, 500# hulls. Halliburton Cmt

Co. Drillable plug at 3400'. Went in with tool and broke up plug and pushed to bottom.

Poe Well Service Petro Jet perforated Kiowa.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:00PM Day: 25 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT Squeeze 4 1/2" w/150 sks cement blend w/400# hulls to max psi 300#.. Close in psi 150#. Squeeze 8 5/8" annulus w/100 sks 100# hulls to max 300#.

Close in psi 150#. Plug complete.

RECEIVED  
OCT 30 1989  
COMMISSION 10-30-89

Remarks: Filled fresh water well w/cement.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Please advise this plugging.

DATE 10-26-89

INV. NO. 26246

Signed Carl Goodrow (TECHNICIAN)