

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22554-00-00  
Spot: NENESW Sec/Twnshp/Rge: 35-25S-3E  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: HUTCHENS Well #: 1  
County: BUTLER Total Vertical Depth: 2750 feet

Operator License No.: 5446  
Op Name: GILES, BENJAMIN M.  
Address: 532 SOUTH MARKET  
WICHITA, KS 67202

PROD Size: 4.5 feet: 2749 50 SX CMT  
SURF Size: 8.625 feet: 205 140 SX CMT

# 89<sup>38</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2004 12:00 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING  
Proposal Rcvd. from: TOM SCHMIDT Company: BENJAMIN M. GILES Phone: (316) 541-2411

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
JUN 23 2004  
WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/10/2004 12:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to surface. Ran 1" tubing to 255' and circulated cement to surface with 105 sacks of 60/40 posmix with 4% gel.

Perfs:


Top	Bot	Thru	Comments
2713	2715		

Remarks: BRADEN PETROLEUM DID CEMENTING.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 6-25-04  
TEL. NO. 2004061781

Signed by Steve Van Gieson  
for Donald Hoberecht