

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20938-00-00
Spot: NW Sec/Twnshp/Rge: 22-18S-10W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: SCHULTZ Well #: 1
County: RICE Total Vertical Depth: 3260 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 4.5 feet: 3250
SURF Size: 8.625 feet: 236

\$105.95

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2004 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand back to 3200' and cut off casing. Pull to 1250' and pump 35 sacks of cement; pull casing to 900' and pump 35 sacks of cement; pull casing to 285' and circulate cement to surface.
**RECEIVED
KCC DISTRICT #2
JUN 28 2004**

WICHITA, KS

Plugging Proposal Received By: DAVE WERTZ Witness Type: PARTIAL
Date/Time Plugging Completed: 06/24/2004 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3200' and put 4 sacks of cement on top. Cut off casing at 1621'. Pulled casing to 1250' and pumped 35 sacks of cement; pulled casing to 900' and pumped 35 sacks of cement; and pulled casing to 285' and circulated cement to surface.

60/40 posmix with 4% gel.

Remarks: ALLIED #17827
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 7-1-04
WEL. NO. 200906006