

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20778-00-00
Spot: SESENW Sec/Twnshp/Rge: 25-34S-35W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KINNEY CHESTER SAND UNI Well #: 201
County: STEVENS Total Vertical Depth: 6650 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

COND Size: 20 feet: 43 WITH 2 YDS CMT 13
PROD Size: 5.5 feet: 6630 WITH 175 SX CMT
SURF Size: 8.625 feet: 1759 WITH 800 SX CMT \$216

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2004 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE
Date/Time Plugging Completed: 06/18/2004 4:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 6590'. PUMPED DOWN 5 1/2" 500# HLLS & 25 SX CMT. DISPLACED WITH MUD. PRESSURED UP TO 500#. 1ST PLUG PULLED CASING TO 1800' & PUMPED 50 SX CMT. 2ND PLUG PULLED TO 600' & PUMPED 30 SX CMT. 3RD PLUG PULLED TO 40' & PUMPED 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
6559	6569		
6512	6542		

RECEIVED
JUN 30 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2330' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durent
(TECHNICIAN)

INVOICED

DATE 6-30-04
TV. NO. 2004061799