

6030414

15-034-20734-00-00

PLUGGED

P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-039-20734

SW, SEC. 12, T. 2 S, R. 28 W

1650 feet from #S section line

4290 feet from #E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Olive Water Flow Well # 2-3

Operator: John O Farmer Inc.

County Decatur 117.33

Name & Address 370 W. Wichita

Well Total Depth 3610 feet

Russell, Kansas

Conductor Pipe: Size \_\_\_\_\_ feet

67665

Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Great Bend, Kansas

Company to plug at: Hour: AM. Day: 15 Month: 4 Year: 19 85

Plugging proposal received from Deacon

(company name) Rockhold Eng. (phone) \_\_\_\_\_

were: 8 5/8 set @ 206 w/ 150 af. 4 1/2 set @ 3574 w/ 150 af Perf: 3457-60

Order Com. Cam. Sand - 170 af 50/50 pox 6% gel 3% cc 40 af gel 4 af Hulla.

8 5/8 w/P. Allied Cam. have water trucks Recovered 2000+ of 4 1/2"

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 PM Day: 15 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT Bottom Plug w/ Bailer 4 af Com Cam. Dump sand to 3400 w/ bailer

4 af Com. Cam. on top. Strip pipe. Top Plug. Pump Down 8 5/8 - 4 af Hulla -

25 af gel. - 100 af Cam. mix. - 15 af gel. - 8 5/8 w/P. - 70 af cam mix.

Plug down at 1:30 PM Plugging Complete Max. Pressure 200\* shut in 100"

RECEIVED STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this report)

APR 26 1985 4-29-85

I (did / did not) observe this plugging.

Signed Carl Goodnow (TECHNICIAN)

DATE 5-7-85

INV. NO. 7966

FORM CP-2/3 Rev. 01-84

9 4-26-85