

72-4 15-039-00009-00-00

To: 6 031302  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1961  
C NE SW, SEC. 12, T 2 S, R 28 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5135  
Operator: John O. Farmer Inc.  
Name & Address 370 W Wichita, Avenue  
Box 352  
Russell, Ks. 67665

Lease Name Olive Water Flood TRR WI  
Anna Miller Well # 1  
County Decatur 131.30  
Well Total Depth 4040 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 130

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cement License Number \_\_\_\_\_  
Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 4 Month: Dec Year: 19 89

Plugging proposal received from L. A. Eichman  
(company name) Farmer (phone) \_\_\_\_\_

were: 8 5/8" set at 130' w/100 sks. 5 1/2" set at 3570' w/100 sks. Squeeze at 1530'  
w/300 sks. Shot at anhy 2043'. Perfs 3466' - 70'. PBTD 3532'. Order 300 sks  
65/35 poz 10% gel 2% dicel 500# hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15AM Day: 4 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/200 sks cement blend w/400# hulls. Mixed into  
max psi 550#. Close in psi 350#. Test backside annulus to 300#.psi. Blew out head.  
Cement at surface. Plug compelte.

Remarks: Fluid level 1200'.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow 1-17-90  
(TECHNICIAN)  
Carl Goodrow

INVOICED

DATE JAN 24 1990

INV. NO. 27121

*Handwritten initials*