

State of Kansas



15-039-20354-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

103 02 1976
8-2-76
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Sixberry of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Sixberry guarantees payment of the plugging fee.

Operator's full Name: Resources Investment Corporation

Complete Address: 2080 First of Denver Plaza, 633 17th St., Denver, Colo.

Lease Name: Bryant Well No. 1

Location: C SE SE Sec. 1 Twp. 2 Rge. (E)(W) 28

County: Decatur Total Depth 3586' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Sixberry was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 1545' thru drill

pipe. Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo. Masser
Conservation Division Agent