



15-039-20144-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
3-3-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated, has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name: Myrtle Miller Well No. 1

Location: CSW-SE Sec. 1 Twp. 2 Rge. (E)(W) 28

County: Decatur Total Depth 3660' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burheister was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 130 Sx.  
Top of Dakota section @ 1075'

Circulate hole with heavy mud. Pull DP to 1080' and displace 100 S.  
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent