

State of Kansas



15-039-20019-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
NOV 15 1967
11-15-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Russell Sullivan of Russ Csg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Brown Well No. 1

Location: SW-NE-SE Sec. 19 Twp. 2 Rge. (E)(W) 28

County Decatur Total Depth 3820 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

178'--8 5/8" Surface pipe, cement circulated with 125 Sx.
3813'--4 1/2" Production casing cemented on bottom with 125 Sx. Well
plugged back to 3672'. Top perforations from 3666' to 3668'.

Sand well back to 3650' and set 3 Sx. cement with dump bailer. Pull
4 1/2" casing and squeeze well with 35 Sx. gel using 5 Sacks hulls in in-
itial gel and 130 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent