

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20144-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1970
CONSERVATION DIVISION
Wichita, Kansas
3-3-70

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Myrtle Miller Well No. 1

Location CSW-SE Sec. 1 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3660'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:00 AM Day 1 Month 3 Year 1970

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1280' and displaced 100 Sx. cement thru
DP from 1280' to 900'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3/3/70
INV. NO. 1538-11