

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20172-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
8-10-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Reeves Well No. 2

Location SW-NE Sec. 12 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3460'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 7:00 AM Day 5 Month 8 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with--  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'  
to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 8/10/70  
INV. NO. 2346-W