

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00471-00-00

RECEIVED
STATE CORPORATION COMMISSION

SEP. 14 1962

CONSERVATION DIVISION
Wichita, Kansas

9-14-62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Union Texas Pet Co

Complete Address: Drawer (D) Great Bend, Kansas

Lease Name Reeves Well No. 1

Location CNW SE Sec. 12 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3575

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No.

Operation Completed: Hour 7:45 PM Day 10 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 214' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced 20
sax cement through drill pipe, heavy mud to 180', set plug and 20 sax
cement, heavy mud to 35', set plug, hulls and filled to bottom cellar with
cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edwin Perry*
Well Plugging Supervisor

DATE 9-18-62

INV. NO. 5405-W