

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1967

11-15-67

CONSERVATION DIVISION
Wichita, Kansas

15-039-20019-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita, Russell, Kansas.

Lease Name Brown Well No. 1

Location SW-NE-SE Sec. 19 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3820'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box # 1082, Great Bend, Kansas. License approved, waiting on
License No. Number.

Operation Completed: Hour 3:30 PM Day 11 Month 11 Year 1967

The above well was plugged as follows:

178'--8 5/8" Surface pipe, cement circulated with 125 Sx.

3813'--4 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3672'. Top perforations from 3666' to 3668'.. Dakota section from 1260' to 1460'.

Sanded well back to 3650' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing

and squeeze well with 13 sacks gel using 5 sacks hulls in initial gell, follow with

100 Sx. cement from 1480' to 1160', then 20 sacks gel from 1160' to 210' and follow

with 25 Sx. cement from 210' to 135', then 2 sacks gel from 135' to 30' and follow

with 5 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--350#.

Final shut-in pressure--75#. (Recovered 1920' 4 1/2" casing) (Mudding and cementing by Globe).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/15/67
INV. NO. 6688-W