

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: M.E. Klein & Associates, Inc.
Address: 1818 West Lindsey Bldg C-180 Norman Ok. 73070
Phone: (405) 627-0669 Operator License #: 31933
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 6-25-04 (Date)
by: Jay Pfeifer Hays District (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3640- Bottom: 3645 T.D. _____
Marmathon Depth to Top: 3787 Bottom: 3825 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-195-20566-00-01
Lease Name: Hillman
Well Number: # 1
Spot Location (QQQQ): SE - SW - SE - 1/4
330' Feet from North / South Section Line
1650' Feet from East / West Section Line
Sec. 3 Twp. 11 S. R. 22 East West
County: Trego 31 & 2 KCC
8-28-83 BEM
Date Well Completed: 8-28-83 7/2/04
Plugging Commenced: 6-29-04
Plugging Completed: 6-29-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil-Water	3640	3645	8 5/8ths	246	none
Marmathon	oil-water	3787	3825	"	"	"
				5 1/2	3931	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied into 5 1/2 casing pumped 50sks of cement pumped 10 sks of gel w/ 500# hulls followed with 150 sks of cement
pressured to 500# held tied into annulus pressured up shut in. Plugging completed.
cement order was 200sks 60/40 10% gel 10 sks gel and 500# of hulls.

Name of Plugging Contractor: Allied Cementing, Inc License #: _____
Address: Russell Ks.
Name of Party Responsible for Plugging Fees: M.E. Klein & Associates, Inc.
State of Kansas County, Ellis, ss.

Carl Zimmerman Field Consultant (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature)

(Address)

SUBSCRIBED and SWORN TO before me this 20 day of JUNE, 20 04

David V. Schmidt
Notary Public

My Commission Expires: 4/2006



Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUL 01 2004
KCC WICHITA

[Handwritten signature]