

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

RECEIVED
JUN 22 2004 Type or Print on this Form
KCC WICHITA Form must be Signed
All blanks must be Filled

Form CP-4
December 2003

Lease Operator: Ritchie Exploration, Inc.
Address: PO Box 783188 Wichita, KS. 67278-3188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 04-08-2004 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LKC Depth to Top: 3609' Bottom: 3797' T.D. 3825'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-22531-00-00
Lease Name: Virgil Jacobs A
Well Number: #1
Spot Location (QQQQ): _____ - NE - NW - NW
330 Feet from North / South Section Line
360 Feet from East / West Section Line
Sec. 19 Twp. 6 S. R. 22 East West
County: Graham
Date Well Completed: 11-30-89
Plugging Commenced: 06-10-04
Plugging Completed: 06-10-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	oil/water	3609'	3797'	8.625"	269'	0'
				4.50"	3824'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement visible in 8 5/8" x 4 1/2" head, no further cementing necessary.

Ran 2 3/8" tubing to 2102'. Mixed and pumped 115 sacks 60/40 Pozmix cement w/ 10% Gel and 450# hulls down tubing.

Cement circulated to surface up 4 1/2" casing. Pulled 2 3/8" tubing out of hole.

Mixed and pumped 160 sacks. 60/40 Pozmix cement w/ 10% Gel and 50# hulls, down 4 1/2" casing, Max pressure = 400#.

Name of Plugging Contractor: Allied Cementing 3M Martin Drilling *Review Ticket # 17104* License #: 30606
Address: PO Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.

John Niernberger (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 783188 Wichita KS 67278-3188

SUBSCRIBED and SWORN TO before me this _____ day of _____, 20____

Notary Public My Commission Expires: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]

ALLIED CEMENTING CO., INC.

17104

Federal Tax I.D.# ~~25-23200~~

10 P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: _____

R

DATE <i>6/10/04</i>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <i>3:45 PM</i>
LEASE <i>Virgil Jacobs</i>	WELL# <i>D-1</i>	LOCATION <i>Bogue & 24 Jct 4 1/2 W 10 N</i>			COUNTY <i>Graham</i>	STATE <i>KS</i>	
OLD OR NEW (Circle one)			<i>2 3/4 W 1/4 S</i>				

CONTRACTOR *Martin*

TYPE OF JOB *plug*

HOLE SIZE _____ T.D. _____

CASING SIZE *4 1/2* DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED *275⁶⁰/₄₀ 10% gel*

5 Hulls

COMMON	<i>165</i>	@	<i>765</i>	<i>1262.25</i>
POZMIX	<i>110</i>	@	<i>4.00</i>	<i>440.00</i>
GEL	<i>19</i>	@	<i>11.00</i>	<i>209.00</i>
CHLORIDE		@		
ASC		@		
<i>Hulls</i>	<i>5</i>	@	<i>20.00</i>	<i>100.00</i>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>299</i>	@	<i>1.25</i>	<i>373.75</i>
MILEAGE	<i>5 1/2 sk / mile</i>			<i>1046.50</i>
TOTAL				<i>3431.50</i>

EQUIPMENT

343 Dave

PUMP TRUCK CEMENTER *Steve*

HELPER _____

BULK TRUCK DRIVER _____

DRIVER _____

BULK TRUCK DRIVER *Craig*

REMARKS:

Run tubing to 2100' spot 115 sk w/c 950 # Hulls & cin to surface, pulled tubing, tied on to 8 3/4 pressured to 400 psi & held tied on to 4 1/2 mixed 50# Hull w/c 160 sk max 400 psi

CHARGE TO: *Ritchie Exploration*

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED
JUN 22 2004
KCC WICHITA

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *[Signature]*

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE *500.00*

EXTRA FOOTAGE _____ @ _____

MILEAGE *70* @ *4.00* *280.00*

TOTAL *780.00*

PLUG & FLOAT EQUIPMENT

MANIFOLD _____ @ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____



June 21st, 2004

RECEIVED
JUN 22 2004
KCC WICHITA

State Corporation Commission
Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202

**RE: #1 Virgil Jacobs A
NW/4 - Sec. 19-6S-22W
Graham County, Kansas**

To Whom It May Concern:

Enclosed please find the Well Plugging Record (CP-4) for the above referenced well.

If you have any questions, please feel free to call the undersigned or John Niernberger at 316-691-9500. Thank you.

Sincerely,

Jennifer Foss
Production Assistant

jf

Enclosures