

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Bear Petroleum, Inc. Address: P.O. Box 438 Haysville, Kansas 67060 Phone: (316) 524-1225 Operator License #: 4419 Type of Well: Oil Docket #: The plugging proposal was approved on: Mike Wilson by: Mike Wilson Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. 3548

API Number: 15-159-21182 Lease Name: Wolf "B" Well Number: 2-6 Spot Location (QQQQ): SE NE NE 990 Feet from North / South Section Line 330 Feet from East / West Section Line Sec. 6 Twp. 21 S. R. 6 East West County: Rice Date Well Completed: Plugging Commenced: 6-11-04 Plugging Completed: 6-15-04

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes 8-5/8" and 5-1/2" with depths 213' and 1800'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Plugged off bottom with sand to 3420' and 5 sacks cement, Cut 5-1/2" casing loose @1800', pulled up to 1050', pumped 35 sacks cement W/100# hulls, pulled up to 625', pumped 35 sacks cement W/200# hulls, pulled up to 265' and circulated 265 sacks cement, 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.


State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 24th day of June 2004

[Signature] My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED JUN 25 2004 KCC WICHITA

[Handwritten mark]