

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20685

LEASE NAME Kinney Chester Sand

WELL NUMBER Unit 804

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 36 TWP. 34 RGE. 35 or (W.)

COUNTY Stevens

Date Well Completed 1-13-84

Plugging Commenced 5-20-04

Plugging Completed 5-24-04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE(S) (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well) 6-1-04 <sup>KCC</sup> <sub>BBB</sub> 4/28/04

The plugging proposal was approved on 5-17-04 (date)

by Kevin Strube (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chester Depth to Top 6522 Bottom 6533 T.O. 6632

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1638	-
				5 1/2	6631	2401

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each as follows:  
Mixed 300 lb. hulls & 25 sx cmt. to plug perfs from 6522 to 6322.  
Shot & pulled 5 1/2 to 1650. Circ. hole w/mud & mixed 50 sx 1650 to 1500  
30 sx 600 to 500 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

RECEIVED  
JUN 25 2004

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss. KCC WICHITA


Kenny Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of June, 2004

Anita Peterson  
Notary Public



My Commission Expires: Oct 1, 2005