

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22153-00-01

Spot: SWNWSW

Sec/Twnshp/Rge: 26-19S-11W

1650 feet from S Section Line,

4950 feet from E Section Line

Lease Name: BRENN

Well #: 4

County: BARTON

Total Vertical Depth: 3345 feet

Operator License No.: 4058

PROD Size: 4.5 feet: 3344 125 SX CMT

Op Name: AMERICAN WARRIOR, INC.

SURF Size: 8.625 feet: 217 175 SX CMT

Address: PO BOX 399

GARDEN CITY, KS 67846

Well Type: EOR

UIC Docket No: E25280.1

Date/Time to Plug: 06/30/2004 2:30 PM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: JODY SMITH

Company: AMERICAN WARRIOR, INC.

Phone: (620) 272-1023

Proposed
Plugging
Method:

Ordered 130 sxs SMDL with 500# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/30/2004 4:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Services rigged up to 4 1/2" casing with a swedge.
Pumped 100 sxs SMDL cement with 500# hulls mixed in - well went on vacuum.
Left set one hour.
Tied onto backside - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Topped off 4 1/2" casing with 20 sxs cement.
Hole was standing full to surface.

Perfs:

Top	Bot	Thru	Comments
3233	3236		
3132	3136		


RECEIVED
JUL 07 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #6949.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 7-7-04

INV. NO. 2005060012

Form CP-2/3

JUL 02 2004

60-48-419
 00 NW SW
 6-PTG.
 CHISE-SILICE
 P 44 BOPS. NO WTR
 LANS 8132-8136
 10-070-11-163

LOG TOPS	DEPTH	DATUM
1000	2572	-11168
TOP	2582	-11168
BOPD		

[illegible]

8-5/2" 217/175SX, 4 1/2" 3344/125SX
 DST (1) 3036-3080/30-30-30-30, 300'
 GIP, REC 100', 30&GCM, SIP 215-
 195#
 DST (2) 3080-3128/30-30-30-30, REC
 30', SOCGM, 455' FROTHY 0, 155' COG, NW, SIP 559-655#
 64-118/161-185#
 DST (3) 3128-3140/30-30-30-30, 620'
 GIP, REC 125', 0&GCM, SIP 377-387#
 75-75/56-75#
 DST (4) 3220-3240/30-30-30-30, REC
 20' 0 SPKG M, SIP 825-729#
 53/64-55#

PETROLEUM ENERGY INC #4 BRENN 26-19-11W
SW NW SW
MCT - CO, PF 3233-3236, AC 1000 GAL,
SWB 3 BFPH/4HRS, (2% OIL), SET PLUG
@ 3200', PF 3132-3136, AC 1000 GAL,
SWB 4.64 BFPH, (50% O & 50% WTR), POP,
P 44 BCPD, NO WTR