

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24751-00-00
Spot: S2SW Sec/Twnshp/Rge: 24-15S-18W
660 feet from S Section Line, 3810 feet from E Section Line
Lease Name: WERTH Well #: 1
County: ELLIS Total Vertical Depth: 3598 feet

Operator License No.: 3715
Op Name: S.B. OIL COMPANY
Address: 921 W 41ST
HAYS, KS 67601

CIBP Size: feet: 3490
CIBP Size: feet: 3560
PROD Size: 5.5 feet: 3593 w/135 sxs cmt
SURF Size: 8.625 feet: 215 w/150 sxs cmt

\$ 116⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2004 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: GENE KARLIN Company: S.B. OIL COMPANY Phone: (785) 625-2460

Proposed Plugging Method: Ordered 200 sxs cement - 500# hulls - 20 sxs gel.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2004 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

P.C. at 1244' w/90 sxs cement.
Tied to 8 5/8" x 5 1/2" - pressured to 700# - took no cement.
Tied to 5 1/2" casing - pumped 40 sxs cement with 250# hulls,
followed with 20 sxs gel and 250# hulls.
Squeezed 120 sxs cement. Max. P.S.I. 1400#. S.I.P. 1000#.
Total of 160 sxs 60/40 pozmix - 10% gel - 20 sxs gel - 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3563	3565		
3556	3558		
3549	3551		
3541	3544		
3332	3336		
3307	3310		
3289	3291		

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger Moses

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

7-7-04

WV. NO.

2005060034

JUN 30 2004

replacement card

SB OIL CO
HAYS KS 67601

24-15S-18W
C S/2 SW

#1 WERTH

site: 1 N & 2-3/4 E OF SCHOENCHEN KS	cty: ELLIS	API 15-051-24751
contr: WESTERN KANSAS DRLG	field: BIELMAN	
geol: RON NELSON		
fr date 07/11/1991	spcl date 07/15/1991	drig comp 07/21/1991
		card issued 10/14/1991
		last revised 02/02/2004

ELV: 1977 KB, 1972 GL LOG

tops.....	depth/datum
ANH.....	1126 +851
B/ANH.....	1167 +810
TOP.....	2951 -974
HEEB.....	3217 -1240
TOR.....	3239 -1262
LANS.....	3269 -1292
BKC.....	3497 -1520
ARB.....	3543 -1566
RTD.....	3598 -1621

IP status
OIL, P 15 BO & 250 BWP, ARB 3563-3565, 08/20/1991
CORRECTION: 2/2/2004 - ORIG FR IN C S/2 SE
CSG: 8-5/8" 215 / 135 SX (ALT 2), 5-1/2" 3593 / 150 SX
NO CORES
DST (1) 3533-3568 (ARB), / 30-45-30-45, (1ST OP) 1 INCH BLO
BLDG IN BTM BKT, (2ND OP) 1/2 INCH BLO BLDG IN BTM
BKT/14", REC 180' MO (85% OIL, 15% M), 60' M & WOO
(60% OIL, 20% W, 20% M), 120' MO (80% OIL, 20% M), 120'
GSY SLI MO (30% G, 65% OIL, 5% M, GR 36) ISP 1041#
FSIP 1000# IFP 51# -120# FFP 179# -210# IHP 1962# FHP 1890#
BHT 106"
TRGT ZN: ARB, PTD 3650 (ARB), MICT - CO, PF (ARB)
3563-3565, W / 2 SPF, AC 250 GAL (15%), SO, SET 2-7/8" TBG
AT 3560, POP, P 15 BO & 250 BWP (GR 30), 8/20/1991

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

AL 100
CYLE