

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20491-00-00
Spot: NWSENE Sec/Twnshp/Rge: 17-1S-34W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: CAHOJ UNIT Well #: 931
County: RAWLINS Total Vertical Depth: 4362 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 4360 w/800 sxs cmt
SURF Size: 8.625 feet: 320 w/170 sxs cmt

141 77

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2004 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 300 sxs Midcon II cement and 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2004 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 320' w/170 sxs cement.
5 1/2" production casing set at 4360' w/800 sxs cement.
PBT 4060' - with cast iron bridge plug.
DV Tool at 3000' - cement did not circulate - top of cement at 1324'.
Ran tubing to 2500' - pumped 150 sxs cement with 400# hulls.
Pulled tubing to 1200' - pumped 65 sxs cement with 400# hulls.
Pulled tubing to 600' - pumped 32 sxs cement - cement to surface.
Connected to 8 5/8" surface casing. - pumped 15 sxs cement.
Max. P.S.I. 350#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4266	4269		
4261	4263		
4225	4229		
4192	4195		
4177	4183		
4043	4047		
4022	4032		

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #6954

Plugged through: TBG

District: 04

HO

Signed Darrel Dipman
(TECHNICIAN)

INVOICED


DATE 7-7-04
INV. NO. 20050600257

JUN 24 2004

GETTY OIL COMPANY
 2705 VINE, UNIT #4 #931 CAHOJ UNIT 17-1-34W
 HAYS, KS 67601 NW SE NE

CONTR MUREIN DRILLING COMPANY CTY RAWLINS

GEOL _____ FIELD CAHOJ



ELV 3141 KBSPD 11/5/83 CARD ISSUED 2/9/84 IP P 51 B0 & 1223 BWPD
~~3136~~ GL LKC 4022-4269 OA
 API 15-153-20,491

SMP	Top	Depth/Datum
ANH	2969+ 172
TOP	3818- 677
OREAD	3924- 783
DOUG	3983- 842
LANS	4022- 881
RTD	4362-1221

8 5/8 " 320/170 SX; 5 1/2 " 4360/800 SX
 NO DSTS
 MICT - CO, PF (LKC) 4266-69, 4261-63, AC 1500 G, SWB LD,
 SO, PF (LKC) 4225-29, SWB DWN, SO, NAT, PF (LKC) 4192-95,
 AC 1000 G, SWB LD, SO, PF (LKC) 4177-83, AC 1800 G, SWB
 LD, SO, PF (LKC) 4130-34, AC 1500 G, SWB LD, SO, PF (LKC)
 4043-47, AC 1500 G, SWB LD, SO, PF (LKC) 4022-32, SWB
 DWN, SO, T & R, POP, P 51 B0 & 1223 BWPD, 1/30/84