

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21570-00-00
Spot: N2SENE Sec/Twnshp/Rge: 28-9S-19W
3630 feet from S Section Line, 660 feet from E Section Line
Lease Name: THYFAULT A Well #: 3
County: ROOKS Total Vertical Depth: 3607 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3600 w/150 sxs cmt
SURF Size: 8.625 feet: 167 w/130 sxs cmt

23
117

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2004 2:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ALAN BANGERT Company: MAI OIL OPERATIONS Phone: (785) 483-1676

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeeze jobs - pumped 400 sxs down backside.
Ran mill shoe. Recovered tubing, collar, rods and junk in the hole.
Unable to get below 900' - decided to P&A.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2004 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Allied pumped 100 sxs 60/40 pozmix - 10% gel neat,
followed with 100 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1100#. S.I.P. 1000#.
8 5/8" full of cement at surface.

RECEIVED
JUL 07 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

RD.

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

7-7-04

CDL NO.

2005060025

Form CP-2/3

JUL 06 2004

JOHN B. COLLINS
 1007 CODY, #1
 HAYS, KS 67601
 DREILING OIL, INC.

JOHN B. COLLINS
 1007 CODY, #1
 HAYS, KS 67601
 CONTR DREILING OIL, INC.

#3 "A" THYFAULT
 28-9-19W
 C N/2 SE NE

CTY ROOKS

GEOL _____ FIELD ZURICH TWST WEST

E 2175 KB CM 1/29/82 ^{CARD}ISSUED 7/1/82 IP OIL WELL

API 15-163-21,570

ARB OH 3600-10

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
SC		1540	+ 635
TOP		3111	- 936
HEEB		3316	-1141
TOR		3340	-1165
LANS		3359	-1184
BKC		3571	-1396
ARB		3595	-1420
RTD		3607	-1432
DDTD		3610	-1435

8 5/8" 167/130sx; 5 1/2" 3600/150sx

NO DST'S REPORTED
 MICT - CO, (ARB OH) 3600-10, TSTD,
 POP, OIL WELL, NO OTHER INFO TO BE
 RELEASED AT PRESENT- WILL RELEASE
 INFO WHEN AVAILABLE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS