

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20566-00-01
Spot: SESWSE Sec/Twnshp/Rge: 3-11S-22W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HILLMAN Well #: 1
County: TREGO Total Vertical Depth: 3935 feet

Operator License No.: 31933
Op Name: M E KLEIN & ASSOCIATES, INC
Address: PO BOX 721436
NORMAN, OK 73070

PROD Size: 5.5 feet: 3931 150 SXS CMT
SURF Size: 8.625 feet: 246 250 SXS CMT

\$12789

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CARK ZIMMERMAN Company: M.E. KLEIN & ASSOCIATES, INC. Phone: (785) 623-4100

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 600# hulls - 10 sxs gel spacer.
D.V. at 1680' circulate with cement.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2004 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Hooked up to the annulus - instant pressure of 500#.
Swaged onto 5 1/2" - mixed and pumped 50 sxs cement with 600# hulls,
followed with 10 sxs gel and topped with 150 sxs cement.
Max. P.S.I. 700#. S.I.P. 200#.

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 7-7-04

INV. NO. 2005060024

Form CP-2/3

JUN 29 2004

replacement card

TRIPLE H OIL OPER
HAYS KS 67601

3-11S-22W
SE SW SE

#1 HILLMAN OWWO

site B-1/2 N & 1/2 W OF OGALLAH KS
contr: DREILING OIL

dy: TREGO
field: DEMURRY

AP 15-195-20566-A

geol:	tr	spd	drig	card	last
date 08/27/1982	date 08/28/1982	comp 08/29/1982	issued 04/21/1983	revised 06/12/2000	

ELV: 2199 KB, 2194 GL LOG

tops.....	depth/datum
ANH.....	1679 +520
HEEB.....	3439 -1240
TOR.....	3462 -1263
LANS.....	3478 -1279
BKC.....	3720 -1521
MARM.....	3786 -1587
ARB.....	3880 -1681
RTD OLD.....	3900 -1701
LTD OLD.....	3903 -1704
DDTD.....	3935 -1736

IP status:
OIL, P 45 BO & 10 BWP, MARM 3789-3804, 12/15/1982
INFO REL: 6/12/2000 - ADDED PFS & PLUG INFO
NOTE: INFO REL 10/6/1983 - ADDED MISC INFO
OLD INFO: OPERATOR WAS F & M OIL CO, 1 HILLMAN,
SPD 07/27/1979, 08/06/1979 8-5/8" 246 / 170 SX, D&A, ARB,
08/06/1979(CARD ISSUED 08/18/1979)
CONTR: ABERCROMBIE DRILLING
GEOL: BOB JINKINS
NO CORES
DST (1) 3468-3490 (TOR, LANS), / 20-20-20-20, REC 10' M
ISIP 846# FSIP 893# IFP 15# FFP 39# BHT 106'

COPYRIGHT 2000
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)