

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23385-00-00
Spot: NENENW Sec/Twnshp/Rge: 6-13S-17W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: POLIFKA E Well #: 1
County: ELLIS Total Vertical Depth: 3613 feet

Operator License No.: 9394
Op Name: D-OIL, INC.
Address: 402 MAIN PO BOX 278
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3607 150 SX CMT
SURF Size: 8.625 feet: 167 130 SX CMT

#117⁴²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2004 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: FRITZ DREILING Company: D-OIL, INC. Phone: (785) 735-9225

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 700# hulls.
DV Tool at 1300' w/350 sxs cement to surface.
Fluids 1700'. OH 3607' - 3613'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dug out backside. Backside was full of cement - visual check.
Tied onto 5 1/2" casing with a swedge - pumped 300 sxs 60/40 pozmix with 700# hulls mixed in.
Max. P.S.I. 100#. S.I.P. 0#.
Topped off with 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3557	3559		
3400	3404		
3358	3376		
1287	1324		

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #16912.

Plugged through: CSG

District: 04

Signed _____

Patrick P. [Signature]
(TECHNICIAN)

JUN 30 2004

INVOICED
DATE 7-7-04
INV. NO. 2005060017

Form CP-2/3

DREILING RESOURCES 1983 JOINT VENTURE

P.O. BOX 278

#1 "E" POLIFKA

6-13-17W

VICTORIA, KS 67671


NE NE NW

CONTR DREILING OIL, INC.

CTY ELLIS

GEOLOGICAL

FIELD POLIFKA



ELV 2066 KB SPD 3/9/83

CARD ISSUED 5/19/83

IP P 83 BOPD, TR WTR

2061 GL

LKC 3358-3404 OA

API 15-051-23,385

ARB OH 3607-3613

LOG	Tops	Depth/Datum
ANII		1287 779
B' ANH		1324 742
TOP		3046- 980
HEEB		3283-1217
TOR		3304-1238
BKC		3568-1502
ARB		3590-1524
RTD		3613-1547

8 5/8 " 167/130SX, 5 1/2 " 3607/150SX
 MICT - CO, PF 2/ 1300. SQZ'D W/ 350SX (1WO-STAGED), PF 2
 3430, SQZ'D W/ 125SX, PF 2/ 3362-3363. SQZ'D W/ 75SX, CO,
 (ARB OH), SWB DWN, SO, NAT, PF (LKC) 3400-3404, W: 4 SPF
 & 2/ 3376, 2/ 3358, SWB DWN, AC 6000 G (15%) FROM 3358-
 3612 OA, SWB DWN, POP, P 83 BOPD, TR WTR (GR E 32").
 COMMINGLED, 5/4/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS