

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21091-00-00
Spot: NWNW Sec/Twnshp/Rge: 24-33S-19W
590 feet from N Section Line, 550 feet from W Section Line
Lease Name: MOFFETT Well #: 24-4
County: COMANCHE Total Vertical Depth: 5700 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

CIBP Size: feet: 5180 WITH 2 SX CMT
COND Size: 20 feet: 43 WITH 4 YDS CMT
PROD Size: 5.5 feet: 5532 WITH 125 SX CMT
SURF Size: 8.625 feet: 636 WITH 325 SX CMT

185²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2004 11:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: SAMUEL GARY JR & ASSOC. Phone: (316) 653-7368

Proposed Plugging Method: CIBP @ 5180' & 2 SX CMT. PLUG AT 1050' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2004 12:45 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5491'. CIBP @ 5180' WITH 2 SX CMT. 1ST PLUG PULL TO 1030' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 650' & SPOT 50 SX CMT. 3RD PLUG PULL TO 300' & SPOT 30 SX CMT. 4TH PLUG PULL TO 40' & SPOT 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5471	5476		
5453	5462		
5394	5400		
5335	5339		
5320	5328		

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JUN 29 2004
KCC Dodge City

Signed _____

(TECHNICIAN)

INVOICED
DATE 7.7.04
INV. NO. 2005060635