

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22402-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 34-31S-39W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MLP CLOSE Well #: F 1
County: STEVENS Total Vertical Depth: 5944 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 5.5 feet: 5944 WITH 160 SX CMT
SURF Size: 8.625 feet: 1730 WITH 50 SX CMT

4193'18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2004 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5800'. PLUG AT 1760' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 06/28/2004 6:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 5936'. SAND TO 5783' & 5 SX CMT. SHOT OFF AT 2500', 2000', 1850', 1750'.
1ST PLUG AT 1475' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5842	5856		

RECEIVED
JUL 02 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED

DATE

7.7.04

CEL. NO.

2005060629