

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20144-00-00
Spot: NWNW Sec/Twnshp/Rge: 7-32S-30W
660 feet from N Section Line, 660 feet from W Section Line
Lease Name: MITCHELL Well #: 1
County: MEADE Total Vertical Depth: 6060 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 6060 WITH 300 SX CMT
SURF Size: 8.625 feet: 1515 WITH 700 SX CMT

#196⁹⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2004 12:20 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5338' & 4 SX CMT. PLUG AT 1550' WITH 100# HULLS & 50 SX CMT. PLUG AT 500' WITH 100# HULLS & 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2004 2:40 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:
PBTD 6022'. APPROXIMATELY 500' MORE CASING WAS RECOVERED THAN ORIGINALLY THOUGHT. SAND TO 5338' & 4 SX CMT. 1ST PLUG AT 2050' WITH 100# HULLS & 50 SX CMT. 2ND PLUG AT 1050' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

RECEIVED
JUL 02 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
5882	5888		
5710	5716		
5483	5488		
5378	5385		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 4 1/2" CASING.
Plugged through: CSG

District: 01

RECEIVED
JUN 29 2004
KCC Dodge City

Signed Steve Durrant
(TECHNICIAN)

INVOICED
DATE 7.7.04
INV. NO. 2005060029