

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22979-00-00  
Spot: SENW Sec/Twnshp/Rge: 27-7S-22W  
1830 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: STEVENS HOPE Well #: 2  
County: GRAHAM Total Vertical Depth: 3650 feet

Operator License No.: 30259  
Op Name: WERTH, ANDY DBA WERTH EXPLORA  
Address: 1308 SCHWALLER AVE  
HAYS, KS 67601

SURF Size: 8.625 feet: 212

*Handwritten:* 118<sup>63</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2004 5:30 PM  
Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION  
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 625-3531

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE  
Date/Time Plugging Completed: 06/29/2004 6:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

1st. Plug at 1811' w/25 sxs.  
2nd. Plug at 1040' w/100 sxs.  
3rd. Plug at 212' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

RECEIVED  
JUL 02 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

*Handwritten:* Signed \_\_\_\_\_  
(TECHNICIAN)

JUN 30 2004

INVOICED Form CP-2/3  
DATE 7.7.04  
INV. NO. 2005060037