

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24022-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 27-20S-23W
2979 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MARHOFER Well #: 1
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 5 INVERNESS DRIVE EAST STE 120
ENGLEWOOD, CO 80112

PROD Size: 5.5 feet: 4449 WITH 135 SX CMT
SURF Size: 8.625 feet: 704 WITH 350 SX CMT

7144⁶³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2004 10:50 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE PAULY Company: NORSTAR PETROLEUM Phone: (303) 925-0696

Proposed Plugging Method: PUMP 150# HULLS & 35 SX CMT. FILL CASING WITH CMT TO SURFACE. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 06/29/2004 1:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4424'. PUMP 35 SX CMT & 150# HULLS. PUMP 25 SX GEL & 175 SX CMT. MAXIMUM PRESSURE 1700#. SHUT IN PRESSURE 700#. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4374	4378		SPF

RECEIVED
JUL 06 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)
INVOICED
DATE 7-7-04
INV. NO. 20506028

Form CP-2/3