

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20274-00-00  
Spot: SESE Sec/Twnshp/Rge: 12-19S-29W  
510 feet from S Section Line, 660 feet from E Section Line  
Lease Name: THOMAS A Well #: 1  
County: LANE Total Vertical Depth: 4675 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 150 N. MAIN, STE 801  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4673 WITH 75 SX CMT  
SURF Size: 8.625 feet: 240 WITH 175 SX CMT **\$ 15340**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2004 11:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GERALD ACHATZ Company: ABERCROMBIE ENERGY Phone: (316) 262-1841

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. DISPLACE WITH 40 BBL GEL. PRESSURE UP. PERFORATE AT 1300'. PUMP 200 SX CMT DOWN 5 1/2" CASING. PUMP 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/24/2004 3:10 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4630'. PUMPED DOWN 5 1/2" 300# HULLS & 25 SX CMT. DISPLACE WITH 60 BBL GEL - 24 SX CMT - 31 BBL WATER. PRESSURED UP TO 500#. PERFORATED AT 1300'. PUMPED DOWN 5 1/2" 195 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN PRESSURE 350#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 150 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 200#.

Perfs:

Top	Bot	Thru	Comments
4363	4367		
4313	4318		
4228	4232		

RECEIVED  
JUL 02 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED

Plugged through: CSG

District: 01

RECEIVED  
JUN 29 2004  
KCC Dodge City

Signed

Steve Aument  
(TECHNICIAN)

INVOICED

DATE 7-7-04

INV. NO. 2005060011