

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20586-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 2-20S-29W  
2310 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: MURPHY Well #: 1  
County: LANE Total Vertical Depth: 4720 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 150 N. MAIN, STE 801  
WICHITA, KS 67202

CIBP Size: feet: 4400  
MSCC Size: feet: 1018 WITH 475 SX CMT  
PROD Size: 4.5 feet: 4714 WITH 325 SX CMT  
SURF Size: 8.625 feet: 318 WITH 260 SX CMT

*Handwritten initials/signature*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2004 9:35 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Revd. from: GERALD ACHATZ Company: ABERCROMBIE ENERGY Phone: (316) 262-1841

Proposed Plugging Method: PUMP 300# HULLS & 20 SX CMT TO BOTTOM. MUD SPACER TO 2150'. PUMP 165 SX CMT FROM 2150' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/24/2004 10:15 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4400'. DV TOOL @ 1018' WITH 475 SX CMT. CASING LEAK AT 2170'. SQUEEZED WITH 300 SX CMT ON 6/28/1985. PUMPED DOWN 4 1/2" CASING 25 SX CMT & 300# HULLS. PUMP 10 SX GEL SPACER TO 2200'. PUMP 140 SX CMT. PRESSURED UP TO 1200#. SHUT IN AT 500#.

Perfs:


Top	Bot	Thru	Comments
4545	4548		
4455	4459		
4338	4355		
4297	4299		
2144	2172		

RECEIVED  
JUL 02 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Steve Muenent*

(TECHNICIAN)

INVOICED

DATE

7.7.04

INV. NO.

205860011