

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10190-00-00  
Spot: SESW Sec/Twnshp/Rge: 28-29S-34W  
660 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: HALL Well #: 1  
County: HASKELL Total Vertical Depth: 5478 feet

Operator License No.: 7840  
Op Name: BORDERLINE, INC.  
Address: 2260 N RD I PO BOX 1043  
ULYSSES, KS 67880

CIBP Size: feet: 5300  
PROD Size: 5.5 feet: 5483 WITH 300 SX CMT  
SURF Size: 8.625 feet: 1474 WITH 750 SX CMT

*\$178<sup>04</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2004 2:30 PM  
Plug Co. License No.: 7840 Plug Co. Name: BORDERLINE, INC.  
Proposal Rcvd. from: JOSE ORTIZ Company: BORDERLINE, INC. Phone: (620) 356-3381

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 06/29/2004 4:30 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5473'. PUMP 25 SX CMT & 200# HULLS ON BOTTOM. PULL ALL CASING OUT OF HOLE. 1ST PLUG RUN IN TUBING TO 1500'. LOAD HOLE WITH MUD & SPOT 50 SX CMT. 2ND PLUG PULL TO 650' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5334	5342		
5254	5258		

RECEIVED  
JUL 06 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*[Signature]*

(TECHNICIAN)

INVOICED

DATE 7-7-04  
INV. NO. 2005060015

Form *[Signature]*