

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-30184-00-00  
Spot: NENW Sec/Twnshp/Rge: 18-16S-26W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: NORTON Well #: 1-18  
County: NESS Total Vertical Depth: 4542 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

PROD Size: 7 feet: 4525 WITH 200 SX CMT  
SURF Size: 9.625 feet: 258 WITH 125 SX CMT

9147<sup>62</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2004 9:45 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: SCOTT ALBERG Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: PUMP 50 SX CMT AT 2100'. PUMP 50 SX COMMON CMT WITH 3% CC AT 1300' WITH 100# HULLS. PERFORATE AT 1200'. PUMP CASING VOLUME AND 80 SX CMT OVER WITH 100# HULLS. PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 06/25/2004 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4542'. TOP OF TBG FISH @ 2673'. TOP OF ROD FISH @ 2185'. PUMP 50 SX CMT AT 2100'. PULL TUBING TO 1300' & PUMP 50 SX COMMON CMT WITH 3% CC & 100# HULLS. PULL TUBING OUT OF HOLE. LET CMT SET 1 HOUR. PERFORATE AT 1200'. TIE ON 7" & PUMP 80 SX CMT, 100# HULLS, 140 SX CMT. MAXIMUM PRESSURE 600#. SHUT DOWN ON SLIGHT VACUUM. TIE ONTO 9 5/8" X 7" ANNULUS AND START PUMPING. BRADEN HEAD WAS LEAKING. WELDER REPAIRED. PUMPED 100 SX CMT AT 250# MAXIMUM PRESSURE. SHUT IN AT 50#. PUMPED 50 SX CMT DOWN 7". HOLE LOADED.

Perfs:


Top	Bot	Thru	Comments
4522	4542	OH	
4151	4162		

RECEIVED  
JUL 06 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Michael Maier*  
(TECHNICIAN)

INVOICED  
DATE 7-7-04  
INV. NO. 2005060014

Form C-2/S  
*[Signature]*