



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald G. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Stoney Well No. A-1

Location: CNE-SW Sec. 27 Twp. 2 Rge. (E)(W) 28

County: Decatur Total Depth 3800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

290'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

SEP 11 1970

CONSERVATION DIVISION  
Wichita, Kansas

9-11-70

Very truly yours,

W. L. Pichel  
Conservation Division Agent