

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20177-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Stoney Well No. A-1

Location CNE-SW Sec. 27 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kans. License No.

Operation Completed: Hour 3:30 AM Day 8 Month 9 Year 1970

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement
thru DP from 1175' to 1150'. Pulled DP to 310' and displaced 20 Sx. cement thru
DP from 310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1970
CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/11/70

INV. NO. 2514-W

9-11-70