

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-00547-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

8-11-71

Operator's Full Name Donald C Slawson

Complete Address 408 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Stoney Well No. 2

Location SE SW SW Sec. 27 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3755'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling, Inc.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 1:30P Day 9 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3755' 8 5/8 csg set at 175' cwc 150 sk.

5 1/2 csg set at 3755' cw 100 sk cmt.

5 1/2 csg perf. (3640)

Filled 5 1/2 csg W/sd (3600-3755) Dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 1710' of 5 1/2 csg.

Pumped down 8 5/8 csg with 13 sk gel & water W/5 sk hulls (1780-1060) 70 sk cmt (1060-

780) 12 sk gel & Water (780-300) 15 sk cmt (300-240) 5 sk gel & water ( 240-40)

10 sk cmt. (0-40)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russ C. Slawson*  
Well Plugging Supervisor

DATE 8-12-71

INV. NO. 4137-4