

69

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1971
CONSERVATION DIVISION
Wichita, Kansas

6-9-71

15-039-20212-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ward Sauvage,

Complete Address Oberlin, Kansas. 67749

Lease Name Sauvage Well No. 1

Location CSW-SW Sec. 24 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3835'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks License No.

Operation Completed: Hour 8:15 AM Day 2 Month 6 Year 1971

The above well was plugged as follows:

312'--8 5/8" Surface casing, cement circulated with---
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru
DP from ~~1400'~~ 1400' to 1075'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 6-9-71
INV. NO. 3826-W