

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20252-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1972  
CONSERVATION DIVISION  
Wichita, Ka-325  
12-19-72

Operator's Full Name Buttes Gas and Oil Company,

Complete Address 1776 Lincoln Street, Denver, Colorado.

Lease Name Fowler Well No. 1

Location CNW-NE Sec. 23 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3770'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 10:00 PM Day 15 Month 12 Year 1972

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement thru DP from 1375' to 1050'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. D. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 12/19/72  
INV. NO. 6942-W