

9

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 5 1969 1970

CONSERVATION DIVISION  
Wichita, Kansas

1-5-79

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20135-00-00

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Fowler Well No. 1

Location CSE-NE Sec. 23 Twp. 2 Rge. (E) (W) 28

County Decatur Total Depth 3765'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 6:00 AM Day 29 Month 12 Year 1969

The above well was plugged as follows:

173'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement  
thru DP from 1250' to 925'. Pulled DP to 180' and displaced 25 Sx. cement thru DP  
from 180' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 1-6-70

INV. NO. 1209-W