

4-032277

D-20,059

12-17

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20,549 ~~00-00~~

NW SW NW /4 SEC. 27, 02, 28 W  
3630 feet from S section line  
4950 feet from E section line

Operator license# ~~31664~~ <sup>31274</sup>

Lease: Stoney Well # 3-X

Operator: Northwest Well Service

County: Decatur 72.31

Address: 17509 Road 14  
Fort Morgan, CO 80701

Well total depth 2225 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 167 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Co Tools License# 31664

Address:

Company to plug at: Hour: A.M. Day: 17 Month: November Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 100# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:00 A.M., Day: 17 Month: November, Year: 1997

Actual plugging report: 8 5/8" set at 167' w/100 sxs cwc. 5 1/2" set at 2250' with 475 sxs cwc. Prod. Perfs 1992' - 2020'. Squeezed 5 1/2" with 140 sxs cement blend with 100# hulls mixed in to Max. P.S.I. 500#. Plug complete.

Remarks:

Condition of casing (in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_  
Bottom plug (in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I, Carl Goodrow (agent) observe the plugging.

Carl Goodrow  
(agent)

**INVOICED**

DATE DEC 18 1997

INV. NO. 49741  
11-17 JAN 29 1998