

4-032288

15-039-00473-00-01

12-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- N/A

SW SW NW /4 SEC. 27, 02, 28 W
2970 feet from S section line
4950 feet from E section line

Operator license# ~~31664~~ ³¹²⁷⁴
R.L. Hrbeek ^{KCC ops 7/12/04}
Operator: Northwest Well Service
Address: 17509 County Road - #14
Fort Morgan, CO 80701

Lease: Stoney "OWWO" Well # 1-27
County: Decatur 123.50
Well total depth 3800 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 165 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Company Tools License# 31664

Address: 17509 County Road #14 - Fort Morgan, CO 80701

Company to plug at: Hour: P.M. Day: 19 Month: December Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order B.P. and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 4:15 P.M., Day: 19 Month: December, Year: 1997

Actual plugging report: 8 5/8" set at 165' cwc. 4 1/2" set at 3750' with N/A sxs.
Prod. Perfs at 3618' - 3766'. Shots at 2200' and 1300'. Recovered 1300' of 4 1/2" casing.
Squeezed 8 5/8" with 190 sxs cement blend with 500# hulls. Mixed into Max. P.S.I. 300#.
Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Any plug YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

INVOICED

DATE JAN 08 1998

INV. NO. 49896
12-19 MAR 03 1998

STATE CORPORATION COMMISSION
JAN 7 1998
1-7-98
Carl Goodrow
(agent)