

KANSAS

*10*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-00107-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
8-11-71

Operator's Full Name Donald C. Slawson  
Complete Address 408 One Twenty Bldg., Wichita, Kansas 67202  
Lease Name Stoney Well No. 1  
Location SW SW SW Sec. 27 Twp. 2 Rge. (E) (W) 28  
County Decatur Total Depth 3749'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling  
Address Box 1082 Great Bend, Kansas License No. 623  
Operation Completed: Hour 12:20 P Day 9 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3749' 8 5/8 csg set at 190' cwc 190 sk.  
5 1/2 csg set at 3749' cw 100 sk cmt  
5 1/2 csg Perf. (3658)  
Filled 5 1/2 csg W/sd (3625-3749) Dumped 5 sk cmt W/dump bailer. (3585-3625)  
Cutoff and recovered 1325' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 13 sk gel & water W/5 sx hulls (1780-1060) 70 sk cmt (1060-780) 12 sk gel & water (780-300) 15 sk cmt (300-240) 5 sk gel & water (240-40) 10 sk cmt. (0-40).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Gene F. Murray*  
Well Plugging Supervisor

DATE 8/12/71  
INV. NO. 4136-11