

6030392

R

API NUMBER 15-039-20,401-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CUNNW, SEC. 23, T. 2 S, R. 28 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Rush Well # 1

Operator: Murfin Drly. Co.

County Dacatur 125.78

Name & Address 250 N. Water Ste. 300

Well Total Depth 3870 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet

67202.

Surface Casing: Size 8 5/8 feet 142' ✓

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drly Co. License Number 6033

Address Above

Company to plug at: Hour: P.M. Day: 6 Month: 3 Year: 19 85

Plugging proposal received from Stan

(company name) Murfin Drly Co. (phone) _____

were: 8 5/8 set @ 142' w/ 200 ex. 4 1/2 set @ 3865 w/ 175 ex. PSTD 3822 Perf.

3541 Top to 3639 TC. 1100' No Pipe pulled. Halliburton Cement Co.

Ordered 250 ex 50/50 pg 60 gel 3% cc 100 ex gel. 4 ex hulle. 4 1/2 w.P.

Water from Company and Harman's truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:PM Day: 6 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 4 1/2 with 225 ex Cement mix 4 1/2 w.P.

Max 1000# shut in 300# Pump down backside 10 gel 4 ex hulle 25

ex Cement mix. 200# max. plug complete.

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1985

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow 3-27-85
(TECHNICIAN) 13

DATE 4-3-85

INV. NO. 9515