

4-032276

11-17

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,539 ⁰⁰⁻⁰⁰

E2 SE SW /4 SEC. 22, 02, 28 W
660 feet from S section line
2970 feet from E section line

Operator license# ~~31664~~ 31274
Operator: R.L. Hrbeek
Northwest Well Service

KCC
apb
7/9/04

Lease: John E. Bremer Well # 1

County: Decatur 136.66

Address: 17509 Road 14
Fort Morgan, CO 80701

Well total depth 4205 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 203 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# 31664

Address: _____

Company to plug at: Hour: P.M. Day: 17 Month: November Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order plug, common cement.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part , None

12-17-97

Completed: Hour: 12:15 P.M., Day: 17 Month: November, Year: 1997

Actual plugging report: 8 5/8" set at 203' cwc. 4 1/2" set at 4204' w/300 sxs. Prod. Perfs 3686' - 3748'. Set plug at 3630' with 4 sxs common cement on plug with bailer. Shot and recovered 1300' of 4 1/2' with shots at 2200' - 1450'. Squeezed 8 5/8" with 225 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 150#. Plug complete.

Remarks: _____
Condition of casing (in hole): GOOD BAD Any plug: YES NO
Bottom plug (in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I observed the plugging.

Carl Goodrow
(agent)

INVOICED
DATE DEC 18 1997

INV. NO. 49743

11-17 JAN 29 1998