

To: **6 031285**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-11 15-039-20076-00-01  
API NUMBER 15- 039-20,076A

NW NW SW, SEC. 20, T. 2 S, R. 28 W&E  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255  
Operator: McGinness Oil Co.  
Name & Address: 1026 Union Center Bldg.  
Wichita, Ks. 67202

Lease Name J. P. Brown Well # 1  
County Decatur 126.26  
Well Total Depth 3885 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Poë Well Service License Number 3152

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 11 Month: August Year: 19 89

Plugging proposal received from Doug

(company name) McGinness Oil Co. (phone)

were: 8 5/8" set at 209' cwc. 4 1/2" set at 3884' w/140 sks. Port collar at 2374'.  
Order 250 sks 65/35 poz 10% gel 500# Hulls. Halliburton Cement Co.  
LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:15PM Day: 11 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing, loaded hole with cement blend.

Shot at 2390'. Would not pull shot free point at 1310'. Pulled four joints, hooked to casing. Mixed and pumped cement blend down 4 1/2" cement circulated, laid down casing. Hooked onto 8 5/8". Pumped cement blend. Squeezed 4 1/2" and 8 5/8" w/total 250 sks to max psi 1000#. Close in psi 300%. Plug complete.

Remarks: STATE RECEIVED 10-26-89  
STATE CORPORATION COMMISSION  
(If additional description is necessary, use BACK of this form.)

If ( ) checked, observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE 10-25-89  
INV. NO. 26222

Handwritten initials

Carl Goodrow