

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1962

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-039-19025-00-00

CONSERVATION DIVISION
KANSAS
6-12-62

File No. _____ County: Decatur

Location: CNE SE Sec. 28 Twp. 2 Rge. _____ (E) _____ (W) 28

Name of Field: _____ Total Depth: 3710

I have this date completed supervision of plugging of:

Lease Name: Ruzicka Well No. 1

Operator's Full Name: Rains & Williamson Oil

Complete Address: 412 Union Center Wichita, Kansas

Plugging Contractor same

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 8 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 160' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced
20 sax cement through drill pipe, heavy mud to 160', set 15 sax cement
at 160', heavy mud to 35', set plug, hulls and filled to bottom cellar
with cement.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 6/13/62

INV. NO. 5162-W