

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR R. L. HRBEK

ADDRESS RTL BOX 11 MCR 000 COLO

PHONE# (970) 522-4119 OPERATORS LICENSE NO. 31274

Character of Well OFL

() Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-19-97 (date)

by CARL GOODROW (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation KC Depth to Top 3646 Bottom 3712 T.D. 3835

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>KC</u>	<u>OFL</u>	<u>3646</u>	<u>3712</u>	<u>4 1/2</u>	<u>2835</u>	<u>1300</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. SET CEMENT PIP. @ 3500 W/ 4 1/2" CEMENT PULL OUT OF BRADEN HEAD WORK FREE PIPE & SHOOT 504. HOLES @ 1044. 4 1/2" SHOOT & PULL FREE PIPE TIP ON TO SIZE & PUMP 160 SY @ 300 LB HYDRA-SHUT & W/ 300 PSI. PTL & CUT 8 1/2" OFF 4 FT BELOW SURFACE & BACK FILL & LEVEL N.C.

Name of Plugging Contractor NORTHWEST WELL SERV License No. 31664

Address HOLLISTON KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R. L. HRBEK 9-9-98

STATE OF Colorado COUNTY OF Morgan, ss.

R. L. Hrbeke (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R L Hrbeke

(Address) in private

SUBSCRIBED AND SWORN TO before me this 16th day of March, 1998

Kathryn J. Highberger
 Notary Public

My Commission Expires: 2-1-00

15-039-2052600-00

Operator: Cherokee Petroleum Corp
 Well No. 1 Lease Name: Royal J. Fisher
 S 27 T 2S R 28 Ex W Decatur County, Kansas

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Neva	2940	2950	DST #1: 3557-94, IHP 1832-1820, IF 36-71, FF 106-130, ISI 1147, FSI 1147, BHT 102 degrees, Rec 540' gas, 330' TF, 150' MCO&W, 30' M&OCW.	
Red Eagle	3010	3016		
Foraker Show	3056	3100		
Tarkio	3230	3242		
Burling-game	3290	3303		
Topeka	3380	3424		
Oread	3478	3494		
Heebneer	3496			
Toronto	3530	3536		
L-KC "A" Wet	3538	3554		
Pollnow Show	3565	3568		
"B" Show	3572	3588		
"C" Show	3613	3635		
"D" Show	3646	3660		
"E" Show	3684	3694		
"F" Show	3706	3722		
"G" Show	3727	3738		

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 16 1984
 CONSERVATION DIVISION
 Wichita, Kansas
 7-16-84

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received: _____
 Signature: Courtney E. Cook
 Courtney E. Cook Signature
 Vice President -- Operations
 Title: _____
 Date: 11/20/80
 Date: _____