


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-039-00473-00-00

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Decatur County. Sec. 27 Twp. 2 Rge. 28 (E) (W)
Location as "NE/CNW/SW" or footage from lines 330' North South Line & 330' East West Line
Lease Owner Stickelman & Betts
Lease Name Stoney Well No. 1
Office Address Oberlin, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 8-24-57 19____
Application for plugging filed 8-24-57 19____
Application for plugging approved 8-24-57 19____
Plugging commenced 8-25-57 19____
Plugging completed 8-25-57 19____
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 155 feet to 40 feet for each plug set.

Jetted pits. Mixed heavy mud. Filled hole with heavy mud thru drill pipe to 155 feet. Pulled pipe. Set plug 40 sx cement 1/2 sx hulls. Set plug 40 feet 10 sx cement 1/2 sx hulls.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sauvage & Dunn Drilling Co., Inc.
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decatur, ss.
Opal Sauvage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Opal Sauvage
Oberlin, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 19 57.

My commission expires 3-10-58

Cheryl Marton
Notary Public

PLUGGING
FILE SEC 27 T 2 R 280
BOOK PAGE 40 LINE 44

STATE CORPORATION COMMISSION
8-30-57
AUG 30 1957
CONSERVATION DIVISION
Wichita, Kansas

15-039-00473-00-00

DRILLER'S LOG

OPERATOR: Sauvage & Dunn Drig. Co. Inc.
FARM NAME: Stoney
Well #1

LOCATION: SW SW NW Sec 27-2-28
Decatur County, Kansas
CASING RECORD: 165' 8/58 csg.
100 sx cement

CONTRACTOR: Sauvage & Dunn Drig. Co. Inc.
DATE COMMENCED: August 16, 1957
DATE COMPLETED: August 24, 1957

ELEVATION: 2601 DF

Figures denote bottom of formation

Cellar	5	
Shale & Sand	1490	
Shale & Shells	1795	
Shale	2135	
Shale & Shells	2285	
Shale & Lime	2610	
Shale & Lime	2800	
Lime & Shale	3025	
Lime & Shale	3145	
Lime & Shale	3255	
Lime & Shale	3380	
Lime	3450	
Lime	3540	Topeka 3439
Lime & Shale	3680	Heebner 3542
Lime	3744	Lansing 3586
Lime	3760	Base KC 3785
Lime	3800	

CERTIFICATE

STATE OF KANSAS)
DECATUR COUNTY) SS

I hereby certify that the foregoing is, to the best of my knowledge and belief a full, true and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

S. J. Fickel
For Sauvage & Dunn Drilling Co. Inc.

Subscribed and sworn to me, the undersigned, a Notary Public, this 27th day of August, 1957.

Opal Sauvage
Notary Public

My commission expires May 17, 1959

PLUGGING
FILE SEC 27 T. ² R. 28W
BOOK PAGE 40 LINE 44

83057